Certificate

Voluntary external monitoring of construction products

Certificate No.: 01 202 643 / Sikla-01-2021

Name and address of the

manufacturer:

Sikla Holding GmbH

Kornstraße 4

A-4614 Marchtrenk

Manufacturing Facility: Sikla GmbH

In der Lache 17

D-78056 Villingen-Schwenningen

This is to certify that the manufacturer has factory production control at the manufacturing site for the products named in the scope and is entitled to use the TÜV

Rheinland test mark.

Building product: Supports for pipework

Test Basis: DIN 18200:2018

DIN EN ISO 3834-2:2006 DIN EN 1993-1-3:2010 DIN EN 13480-3:2020

Audit Report: 01 202 643 / 21-2021

Validity period: This certificate is valid as long as the external monitoring is

carried out regularly, at the longest until: 2024-05-09

Cologne, April 26, 2022

Dipl.-Ing. Achim Makowka

TÜV Rheinland Industry Service GmbH Certification Body for Construction Products Am Grauen Stein, D-51105 Cologne

Rev. 2



Annex to the certificate of voluntary external surveillance of construction products

Certificate No.: 01 202 643 / Sikla-01-2021

Scope

Supports for pipework

Modular kit of pipe supports as fixed, guiding and sliding supports for fixing pipe DN 25 to DN 600 to steel girders.

Type designation: - Pipe Shoe: LA, LC, LD, LK (excl. insulating core)

- Fixed Point Set: XS- Guiding Set: FS

Dimensions: HV90, HV150, HV200 up to DN600

Design variants: - Low temperature (LT / -60 to -20°C)

Normal temperature (NT / -20 to +300°C)
High temperature (HT / +300 to +500°C)

Features:

- Capacity: according to manufacturer's specifications for type and size

- Stability: Verification according to DIN EN 1993-1-3 and DIN EN 13480-3 Anh. J

- Materials: Material groups 1.1, 1.2, 72, 73 and 76

according to CEN ISO/TR 15608

- Construction: Design as screw/clamp connections

Height adjustment range according to manufacturer's specifications

The external monitoring based on the technical documentation and installation instructions of the manufacturer as well as the results of the regular monitoring carried out by LGA Bautechnik GmbH.

The certification body confirms that

- the tests carried out meet the requirements laid down;
- the manufacturer carries out factory production control to ensure compliance with the requirements for the manufacture of the construction products;
- it regularly monitors the production, the factory production control and the lawful use of the mark as well as regularly carries out product tests on the basis of the monitoring and certification contract.

Date: 2022-04-26 Rev: 2

